



#### **Product Overview**

The AX-OC range of occupancy sensors are passive infra-red sensors for monitoring occupation through body heat. Detection of occupation will activate the internal relay . The 230Vac Versions have mains rated volt free contacts , whereas the low voltage units can be used to switch a BMS system.

#### **Features**

- Flush, Surface and Wall mount options
- Volt free contact output.

- Compatible with many BMS products
- Flush unit supplied with 3 metres of cable

## **Product Specifications**

**Sensor type:** Passive Infra-Red Detector

Field of View: Flush & Surface 360 deg

Wall 110 deg

**Coverage:** Flush & Surface 7 metres diam max. (at 2.7m height)

Wall upto 12 metres.

**Power Supply:** OC-24-x 12 or 24Vac/dc +/- 15%

OC-240-x 240vAC 50/60hZ +/-15%

Relay: SPDT

Contact Rating: OC-24-x 1A resistive @ 50Vac/dc

OC-240-x 8 A @ 240 Vac resistive (3A ind) or 8 H.F. Ballasts

**Electrical Connections:** +V, 0V, Relay common, NO

**Ambient Temp. Range:** 0 to +50°C

Materials: Flame retardant ABS, polypropylene

Conformity: CE marked, EMC, LVD.

**Country of Origin:** Italy

#### **Order Codes**

AX-OC-24-F Flush Mounted Occupancy sensor 12/24Vac/dc AX-OC-24-S Surface Mounted Occupancy sensor 12/24Vac/dc AX-OC-24-W Wall Mounted Occupancy sensor 12/24Vac/dc AX-OC-24-C Ceiling Mounted Occupancy Sensor 12/24Vac/dc AX-OC-240-F Flush Mounted Occupancy sensor **AX-OC-240-S** Surface Mounted Occupancy sensor 240Vac AX-OC-240-W Wall Mounted Occupancy sensor 240Vac

AX-OC - Issue 1.1 - Date 24/9/2008

Page 1 of 3

# **Occupancy Sensors**



#### **Installation**

#### Siting:

The AX-OC should be sited so that the detection pattern (shown below) captures the normal occupancy positions inside the room. You should also follow the following guidelines.

- Avoid direct sunlight entering the sensor
- Do not sight within 1 metre of any lighting
- Do not position sensor within 1 metre of ventilation or forced air heating.
- Do not position sensor on a vibrating surface

#### **Flush Mounting**

The AX-OC-F should be installed in a ceiling tile through a 41mm hole, using the plastic clips supplied. Ensure the tile is sufficiently strong to take the weight of the sensor and that there is sufficient clearance in the ceiling void.

### **Surface Mounting**

The AX-OC-S has fixing lugs to allow mounting to metal boxes or BESA boxes and has side knockouts for cable entry. also has a bracket for ceiling or wall mounting where anangle is required.

#### **Wall Mounting**

The AX-OC-W has a fixing bracket to enable it to be mounted onto the wall, or alternatively you can mount the unit directly to the wall using using the screw holes inside the back cover.

# Configuration


### **Setting Time Delay**

The occupancy timing has 4 selections 4, 8, 16 and 32 minutes -selectable via dip switches.

#### **Dimensions**

# Detector Pattern Flush & Surface Mount

#### **Wall Mount**



Every effort has been taken in the production of this data sheet to ensure it's accuracy. Axio can not, however, accept responsibility for any damage, expense, injury, loss or consequential loss resulting from any errors or omissions. Axio has a policy of continuous improvement and reserves the right to change this specification without notice.

AX-OC - Issue 1.1 - Date 24/9/2008

Page 1 of 3

# **Occupancy Sensors**



#### **Connections**

Wiring:

The flush units come with 3m of 4 core cable

The surface and wall units have a 4 way terminal block

Low Voltage -Red +V Mains Voltage -Brown 240V -Black 0V -Blue Neutral

> -Green Relay Common -Yellow N.O. Contact -Black Relay Common -Black N.O. Contact

# **Installation and Timing Control**

- 1/Connect wiring to terminal block as indicated
- 2/Adjust time switch positioning to T1 & T2 off and T3 & T4 to required time delay
- 3/ Fix unit in position
- 4/ Power up the unit
- 5/ Wait 10 mins for the unit to stabilise
- 6/ Set T2 (test mode) switch to on and ensure the unit switches off when there is no movement, and switches on when movement is detected in the detection zone
- 7/ Set T2 (test mode) to off

# **Time Delays Switch positions** (switch 1 should be off at normal sensitivity)

4 Minutes	2 off	3 on	4 on
8 Minutes	2 off	3 on	4 off
16 Minutes	2 off	3 off	4 on
32 Minutes	2 off	3 off	4 off

### **Recommended delays:**

Office low traffic 16 minutes
Office high traffic 8 minutes
Classroom 8 minutes
Corridor 8 minutes

### Sensitivity

The system should function normally when installed as directed. In exceptional circumstances where more sensitivity is essential Switch 1 can be put in the ON position. Note this may make the system susceptible to false triggering caused by, for example, extreme air movement.

# **Fault Finding**

1/Relay will not close Check power is on, if LED's flash check photocell setting

2/ Relay goes on and off every 10 seconds Time delay is in Test Mode

3/ Relay goes off when i am working but comes on Re-position sensor or increase time delay or change sensitivity

setting

4/ Relay goes on and off every 30 seconds

Adjust photocell

5/ For IR detection only ensure RV1 and RV2 are kept fully clockwise 6/ The yellow/green LED's flash ensure RV1 and RV2 are kept fully clockwise

AX-OC - Issue 1.1 - Date 24/9/2008

when i move

Page 1 of 3